معرف مظروف موحد رقم: D0F95EE7-B5E1-4D84-B5A2-F1D8A418431C

BSS JOINT VENTURE

شركة بي اس اس للمشاريع المشتركة – جي في

اسم المشروع: تشييد مشروع اكاديمية الملك فيصل بالمجمعة

رقم العقد من الباطن: ٨٤٠٠٠٠٦٦٠٤ رقم التعديل: ٠١ بتاريخ ٢٠٢٤/٠٨/٢٦م

رقم عقد الباطن: ٨٤٠٠٠٠٦٦٠٤، تعديل رقم ٠١ بتاريخ ٢٠٢٤/٠٨/٢٦م

رقم طلب الشراء: غير متوفر

الجهة الطالبة: قسم الإنشاءات - المشتري: (منصور الشواف)

الموضوع: أعمال اضافية للمباني التعاقدية الحالية

اسم المقاول	شركة بي اس اس للمشاريع المشتركة – جي في بين شركة البواني بين البواني - ساليني إمبروجيلو – صاجكو صندوق بريد ٩٩٨١٦- الرياض ١١٦٢٥ (المملكة العربية السعودية)
المقاول من الباطن	شركة كليفلاند بريدج للحديد المحدودة صندوق بريد ١٠٠١٧ الجبيل ٣١٩٦١ (المملكة العربية السعودية)
رقم العقد من الباطن	الرقم المعدل # ٠١

شركة بي اس اس للمشاريع المشتركة	BSS JOINT VENTURE

اتفاقية التعاقد من الباطن والاحكام العامة

١- شروط العقد الرئيسي:

تستند شروط العقد الرئيسي الي عقد المشاريع العامة الحكومية السعودية، بصيغته المعدلة بموجب الاحكام الخاصة والعامة، وفقا لنظام المشتريات والمناقصات الحكوميةواللائحة التنفيذية لنظام المشتريات والمناقصات.

٢- شروط عقد الباطن:

اتفاقية عقد الباطن هي نموذج عقد الباطن للتصميم والإنشاء الذي نشرته جمعية مقاولي الهندسة المدنية، نوفمبر ١٩٩٨ (أعيدت طباعته في أبريل ٢٠٠١ مع تعديلات)، والمعدلة بموجب الشروط والجداول الخاصة لتكييف نموذج عقد الباطن مع شروط العقد الرئيسي.

ابرمت هذه الاتفاقية في يوم الاربعاء بتاريخ ٢٦ اغسطس ٢٠٢٤م

بين كل من:

(أ) شركة البواني المحدودة، شركة مسجلة وقائمة بموجب قوانين المملكة العربية السعودية، برقم السجل التجاري رقم ١٠١٠٠٨٥٥١٨، ومقرها المسجل في ص.ب. ص.ب. ٦٥٦٩٧، الرياض ١١٥٦٦ ("البواني")

(ب) شركة ساليني امبريجيلو ش.م.م، شركة مسجلة وقائمة بموجب قوانين إيطاليا، ومقرها المسجل في شارع فيا ديل ميساليا، ٩٧-٢٠١٤٢، ميلانو، إيطاليا، ومقرها المحلي المسجل في ص.ب. ٩٩٨١٦، الرياض ١١٦٢٥، المملكة العربية السعودية، ورقم سجلها التجاري ١٠١٠١٦٤٥٧٩ ("ساليني إمبريجيلو")

(ج) شركة شبه الجزيرة للمقاولات، شركة مسجلة وقائمة بموجب قوانين المملكة العربية السعودية، ومقرها المسجل في ص.ب. ٢٧٤٠، الرياض ١١٤٦١ ("ساجكو")

جميع الشركات المذكورة اعلاه، والتي دخلت في اتفاقية مشروع مشترك لبناء مشروع كلية الملك فيصل الجوية في المجمعة، يشار إليها مجتمعة باسم "مشروع بي اس اس المشترك" او "المقاول" في جميع اجزاء هذه الاتفاقية.

و
(د) شركة كليفلاند بريدج ستيل المحدودة، وهي شركة مسجلة وقائمة بموجب قوانين المملكة العربية السعودية، برقم السجل التجاري ٢٠٥٥٠٠٧٩١٨، ومقرها الرئيسي في ص.ب. صندوق بريد ١٠٠١٧، الجبيل ٣١٩٦١، المملكة العربية السعودية (يُشار إليه فيما يلي بـ "المقاول من الباطن") من الطرف الاخر.
يُشار إلى المقاول والمقاول من الباطن، منفردين بـ "الطرف" ومشتركين بـ "الطرفين" في جميع اجزاء هذه الاتفاقية.
يشار الي المقاول والمقاول من الباطن، منفردين بـ "الطرف" ومجتمعين بـ "الطرفين" في جميع اجزاء هذه الاتفاقية.
وحيث إن
قام المقاول بابرام عقد (يشار إليه فيما يلي بـ "العقد الرئيسي")، وترد تفاصيله في الجدول الأول؛
وحيث إن
بموجب العقد من الباطن رقم ٨٤٠٠٠٠٦٦٠٤ المؤرخ ٤ مايو ٢٠٢١، أبرم الطرفان اتفاقية بخصوص تنفيذ اعمال الهياكل الفولاذية المدرفلة على الساخن للمباني AW05، AW06، LW03، CW15، SF01، وAA01.
بموجب عقد الباطن رقم ٨٤٠٠٠٠٦٦٠٤، التعديل رقم ٠١، بتاريخ ١٢ مارس ٢٠٢٢، أبرم الطرفان اتفاقية بشأن تنفيذ أعمال هياكل فولاذية إضافية للمباني AW05، AW06، LW03، CW15، SF01، وAA01.
خلال تنفيذ عقد الباطن، راجع الطرفان اتفاقية عقد الباطن لتعكس نطاق العمل المُعدّل في المباني التعاقدية الحالية، بهدف إبرام التعديل رقم ٠٢ الحالي على عقد الباطن.
تُلغي أحكام هذا التعديل رقم ٢ على عقد الباطن جميع عروض الأسعار والمراسلات والوثائق التي سبق مناقشتها والاتفاق عليها بين الطرفين، وتقتصر على موضوع هذا التعديل تحديدًا.

تم الاتفاق بموجب هذا على ما يلي:

١- قيمة التعديل رقم ٢:

١-١ تبلغ قيمة الأعمال التي سيتم حذفها بموجب هذا التعديل رقم ٢ (-٦,٧٦٠,٢٢٨.٥٠) ريال سعودي (بالعملة: ستة ملايين وسبعمائة وستون ألفًا ومائتان وثمانية وعشرون ريالًا سعوديًا، ١٠٠/٥٠)، السعر مفترض وغير ملزم للمقاول: تحتسب اعمال المقاولة من الباطن بناء على الاعمال الفعلية المُنجزة مقابل اسعار الوحدات المُحددة بموجب الملحق رقم ٠١ المرفق.

١-٢ بموجب هذا التعديل رقم ٠٢، يُغيّر سعر المقاولة من الباطن بموجب البند رقم ٠١ من الجدول الثالث على النحو التالي: السعر الإجمالي المُقدّر للمقاولة من الباطن هو ٢٠,٧٨٩,٤٤١.٥٠ ريال سعودي (عشرون مليونًا وسبعمائة وتسعة وثمانون ألفًا وأربعمائة وواحد وأربعون ريالًا سعوديًا بنسبة ١٠٠/٥٠) - غير شامل ضريبة القيمة المضافة، بناءً على أسعار الوحدات والكميات المُحددة بموجب الملحق ذي الصلة.

١-٣ سعر المقاولة من الباطن مُفترض وغير مُلزم للمقاول: يتم دفع اعمال المقاولة من الباطن بناء على الاعمال الفعلية المنجزة مقابل اسعار الوحدات المحددة بموجب الملحق ذي الصلة.

٢- ملحقان للتعديل رقم ١:

الملحق ١: التعديل رقم ٢ - جدول الكميات

٣- أحكام اخرى:

تظل جميع الشروط والأحكام الأخرى المتفق عليها بين الطرفين بموجب اتفاقية العقد من الباطن رقم ٨٤٠٠٠٠٦٦٠٤ المؤرخة في ٤ مايو ٢٠٢١ دون تغيير، ويُعد هذا التعديل جزءًا لا يتجزأ منها.

وشهادة على ذلك، قام طرفي الاتفاق بتنفيذ هذه الاتفاقية، بشكل تبادلي عن طريق ممثلهم المفوض هنا كما هو موضح ادناه:
قام بالتوقيع لاجل ونيابة عن شركة بي اس اس للمشاريع المشتركة – جي في بين شركة البواني بين البواني - ساليني إمبروجيلو – صاجكو
من خلال ممثلهم:

		تم توقيع المستند بواسطة
السيد/ مازن نايل	الوظيفة/ مدير المشروع	حسن تميم
السيد/ نسيم سكر	الوظيفة/ مدير العقود	تم التويع
السيد/ فهد سليمان	الوظيفة/ ممثل شركة شبه الجزيرة	تم التوقيع
السيد/ سامر مصطفي	الوظيفة/ مدير المشتريات	تم التوقيع
ختم الشركة	تم ارفاق الختم	
التاريخ		

قام بالتوقيع لاجل ونيابة عن:
شركة كليفلاند بريدج للحديد المحدودة من خلال ممثلهم:

السيد/ سيد الحوت	الوظيفة / المدير العام
ختم الشركة	تم ارفاق الختم
التاريخ	٠٥ سبتمبر ٢٠٢٤م

مؤسسة دار تبادر للترجمة
الخبر س.ت ٢٠٥١٢٢١٦٤٧
D2
المملكة العربية السعودية
Tabador Translation Est.

شركة البواني - ساليني إمبروجيلو – شركة شبه الجزيرة							الملحق رقم ٠١ التعديل رقم ٠٢ – فاتورة الكميات							مرجع التعديل				٨٤٠٠٠٠٦٦٠٤	
														عدد التعديلات				٠٣	
اسم المشروع: مشروع تشييد اكاديمية الملك فيصل بالمجمعة														الموضوع				الاتفاقية النهائية المنقحة	
عقد الاتفاق											اختلاف امر التقييم								
م الاتفاق	ر النشاط	الوصف	الوحدة	الكمية	س و ح ر.س	المبلغ ر.س		ك المناقص	ك تصم النها	السعر ر.س	ك اضافية	اضافة %	م الاختلاف ر.س		العق المعدل ر.س
العقد الرئيسي	AW٠٥	نوع الهيكل: مدرفل على الساخن سقف فولاذي هيكلي: تشمل تكلفة التصنيع توريد وتركيب أعمدة فولاذية هيكلية، وعوارض، وأعمدة، والواح معزولة	طول قياس	١,٠٠	١,١٣٠,٢٤٧.٨٦	١,١٣٠,٢٤٧.٨٦		--	--	--	--	--	--		١,١٣٠,٢٤٧.٨٦
العقد الرئيسي	AW٠٥	السعر الاضافي للتوريد والتصنيع لتركيب الواح الهياكل الفولاذية	طول قياس	١,٠٠	٢٣٠,٧٧٤.٠٢	السعر فقط		--	--	--	--	--	--		
العقد الرئيسي	AW٠٥	سعر إضافي لتوريد وتطبيق الطلاء المقاوم للحريق لمدة ساعتين.	طول قياس	١,٠٠	٥٢,٧٩٨.٠٠	٥٢,٧٩٨.٠٠		--	--	--	--	--	--		٥٢,٧٩٨.٠٠
العقد الرئيسي	AW٠٥	سعر إضافي لعزل الصوف الصخري بدلاً من العزل الحراري بالبولي إيثيلين.	طول قياس	١,٠٠	٨٧,٩٩٨.٩٥	السعر فقط		--	--	--	--	--	--		
جديد	AW٠٥	تغيير مواصفات ألواح الساندويتش من سمك ٠.٥ مم إلى سمك ٠.٧٠ مم طبقات خارجية وداخلية.	طول قياس	١,٠٠				--	١,٠٠	٢٣٦,٥٨٥.٠٠	١,٠٠	١,٠٠	٢٣٦,٥٨٥.٠٠		٢٣٦,٥٨٥.٠٠
		الكلي				١,١٨٣,٠٤٥.٨٦							٢٣٦,٥٨٥.٠٠		١,٤١٩,٦٣٠.٨٦
العقد الرئيسي	AW٠٦	نوع الهيكل: مدرفل على الساخن سقف فولاذي هيكلي: تشمل تكلفة التصنيع توريد وتركيب أعمدة فولاذية هيكلية، وعوارض، وأعمدة، والواح معزولة	طول قياس	١,٠٠	١,١٣٠,٢٤٧.٨٦	١,١٣٠,٢٤٧.٨٦		--	--	--	--	--	--		١,١٣٠,٢٤٧.٨٦
العقد الرئيسي	AW٠٦	سعر إضافي لعزل الصوف الصخري بدلاً من العزل الحراري بالبولي إيثيلين.	طول قياس	١,٠٠	٨٧,٩٩٨.٩٥	السعر فقط		--	--	--	--	--	--		
العقد الرئيسي	AW٠٦	سعر إضافي لتوريد وتطبيق الطلاء المقاوم للحريق لمدة ساعتين.	طول قياس	١,٠٠	٥٢,٧٩٨.٠٠	٥٢,٧٩٨.٠٠		--	--	--	--	--	--		٥٢,٧٩٨.٠٠
جديد	AW٠٥	تغيير مواصفات ألواح الساندويتش من سمك ٠.٥ مم إلى سمك ٠.٧٠ مم طبقات خارجية وداخلية.	طول قياس	١,٠٠				--	١,٠٠	٢٣٦,٥٨٥.٠٠	١,٠٠	١,٠٠	٢٣٦,٥٨٥.٠٠		٢٣٦,٥٨٥.٠٠
		الكلي				١,١٨٣,٠٤٥.٨٦							٢٣٦,٥٨٥.٠٠		١,٤١٩,٦٣٠.٨٦
العقد الرئيسي	SF٠١	نوع الهيكل: مدرفل على الساخن سقف فولاذي هيكلي: تشمل تكلفة التصنيع توريد وتركيب أعمدة فولاذية هيكلية، وعوارض، وأعمدة، والواح معزولة	طول قياس	١,٠٠	٢٣,٩٩٧.٧١	٢٣,٩٩٧.٧١		١,٠٠	--	٢٣,٩٩٧.٧١	١,٠٠	١,٠٠	٢٣,٩٩٧.٧١		--
العقد الرئيسي	SF٠١	سعر إضافي لتوريد وتطبيق الطلاء المقاوم للحريق لمدة ساعتين.	طول قياس	١,٠٠	١,١٢٦.٠٠	١,١٢٦.٠٠		١,٠٠	--	١,١٢٦.٠٠	١,٠٠	١,٠٠	١,١٢٦.٠٠		
العقد الرئيسي	SF٠١	سعر إضافي لعزل الصوف الصخري بدلاً من العزل الحراري بالبولي إيثيلين.	طول قياس	١,٠٠	السعر فقط	السعر فقط		١,٠٠	--	السعر فقط	١,٠٠	١,٠٠	السعر فقط		--
		الكلي				٢٥,١٢٣.٧١							(٢٥,١٢٣.٧١)		
العقد الرئيسي	CW١٥	توريد وتركيب جملون هيكلي فولاذي. يشمل السعر تصميم وإعداد الرسومات التصميمية، ورسومات الورش، وجميع العناصر الفولاذية (الأعمدة، العوارض، الجمالونات)، وفقًا للرسومات والمواصفات.	طول قياس	١,٠٠	٨,١٧٦,٤٨٢.٩٣	٨,١٧٦,٤٨٢.٩٣		١,٠٠	--	٨,١٧٦,٤٨٢.٩٣	١,٠٠	١,٠٠	٨,١٧٦,٤٨٢.٩٣		--
العقد الرئيسي	CW١٥	سعر إضافي لتوريد وتطبيق الطلاء المقاوم للحريق لمدة ساعة واحدة.	طول قياس	١,٠٠	١٧٤,٩١٦.٠٠	١٧٤,٩١٦.٠٠		١,٠٠	--	١٧٤,٩١٦.٠٠	١,٠٠	١,٠٠	١٧٤,٩١٦.٠٠		--
العقد الرئيسي	CW١٥	توريد وتسليم وتركيب المزاريب	طول قياس	١,٠٠	٩,٤٤٠.٧٩	السعر فقط		--	--	--	--	--	--		--
		الكلي				٨,٣٥١,٣٩٨.٩٣							(٨,٣٥١,٣٩٨.٩٣)		

شركة البواني - ساليني إمبروجيلو – شركة شبه الجزيرة								الملحق رقم ٠١ التعديل رقم ٠٢ – فاتورة الكميات						مرجع التعديل				٨٤٠٠٠٠٦٦٠٤	
														عدد التعديلات				٠٣	
اسم المشروع: مشروع تشييد اكاديمية الملك فيصل بالمجمعة														الموضوع				الاتفاقية النهائية المنقحة	
عقد الاتفاق											اختلاف امر التقييم								
م الاتفاق	ر النشاط	الوصف	الوحدة	الكمية	س وح ر.س	المبلغ ر.س		ك المناقص	ك تصم النها	السعر ر.س	ك اضافية	اضافة %	م الاختلاف ر.س		العق المعدل ر.س
العقد الرئيسي	LW٠٣	سقف فولاذي هيكلي: تكلفة تصنيع وتوريد وتركيب أعمدة فولاذية هيكلية، وعوارض، وأعمدة، وألواح عند الضلع المنخفض)، وسطح السقف، وكسوة الأعمدة والواجهات من الألومنيوم، وجميع التركيبات	طول قياس	١,٠٠	٩,٧١٤,٤٨٩,٢٤	٩,٧١٤,٤٨٩,٢٤		٨٦٠,٠٦	١,٠٦٤,٦٨	٩,٧١٤,٤٨٩,٢٤	٢٠٤,٦٢	%٢٣,٧٩	٢,٣١١,٢٠٩		١٢,٠٢٥,٦٩٩
العقد الرئيسي	LW٠٣	باستثناء الألواح العازلة	طول قياس	شامل	شامل	شامل		--	--	٩٧١,٤٤٨,٩٢	--	- %٢٣,٧٩	٢٣١,١٢٠,٩٤		٢٣١,١٢٠,٩٤
العقد الرئيسي	LW٠٣	اضافة الالواح العازلة لاستبدال نافذة السقف	طول قياس	شامل	شامل	٦,٠٢٦,٠٩		٧,٤٧٠,٠٠	٢٠١,٠٠	١,٤٤٤,٠٠٠	%٢٣,٩٦	٢٩٠,٢٤٤,٠٠			٢٩٠,٢٤٤,٠٠
العقد الرئيسي	LW٠٣	سعر اضافي الي توريد وتطبيق الطلاء المقاوم للحريق لمدة ساعة واحدة	طول قياس	١,٠٠	٢,١٠٢,٠١٩,٠٠	٢,١٠٢,٠١٩,٠٠		٨٦٠,٠٦	١,٠٦٤,٦٨	--	٢٠٤,٦٢	%٢٣,٧٩	٥٠٠,٠٩٨,٩٨		٢,٦٠٢,١١٧,٩٨
العقد الرئيسي	LW٠٣	سعر إضافي لعزل الصوف الصخري بدلاً من العزل الحراري بالبولي ايثيلين.	طول قياس	١,٠٠	٣٢٢,٣٨٩,٤٧	السعر فقط		--	--	--	--	--	--		
جديد	LW٠٣	تحديد كميات الكسوة الألومنيوم للأعمدة والواجهات وفقًا للرسومات التوضيحية	طول قياس	شامل	شامل	١,٨١٥,٩٧		--	٤٨٠,٠٠	١,٨١٥,٩٧	١,٠٠	٨٧١,٦٦٥,٦٠			٨٧١,٦٦٥,٦٠
		الكلي				١١,٨١٦,٥٠٨,٢٤							١,٩٩٨,٧٦٥,٨٧		١٣,٨١٥,٢٧٤,١١
العقد الرئيسي	AA٠١	نوع الهيكل: مدرفل على الساخن الرسومات. الفولاذ الهيكلي: تشمل التكلفة تصميم وتصنيع وتوريد وتركيب إطارات الفولاذ الهيكلي من أعمدة ترانس، وعوارض، وأعمدة، وصفائح معدنية وفقًا للمواصفات الهيكلية.	طول قياس	١,٠٠	١,٣٥٥,٤٨٥,٤١	١,٣٥٥,٤٨٥,٤١		١٣٢,٩٥	١٤٠,٨٤	١,٣٥٥,٤٨٥,٤١	٧,٨٩	%٥,٩٣	٨٠,٤٤٢,١٢		١,٤٣٥,٩٢٧,٥٣
العقد الرئيسي	AA٠١	باستثناء صفائح سطح المعدن المموج	طول قياس	شامل	شامل	--		--	--	١٣٥,٥٤٨,٥٤	--	%٥,٩٣-	٨,٠٤٤,٢١		٨,٠٤٤,٢١
العقد الرئيسي	AA٠١	سعر إضافي لعزل الصوف الصخري بدلاً من العزل الحراري بالبولي ايثيلين.	طول قياس	١,٠٠	٣٥,٣٩٢,٠٠	٣٥,٣٩٢,٠٠		١٣٢,٩٥	١٤٠,٨٤	٣٥,٣٩٢,٠٠	٧,٨٩	%٥,٩٣	٢,١٠٠,٣٦		٣٧,٤٩٢,٣٦
		الكلي				١,٣٩٠,٨٧٧,٤١							٧٤,٤٩٨,٢٧		١,٤٦٥,٣٧٥,٦٨
العقد الرئيسي	AW٠٥، AW٠٥، SF٠١، CW١٥، LW٠٣، AA٠١	مواد الفولاذ الهيكلي بما في ذلك بوابة النفايات، والمسامير، ومسامير التثبيت، ومواد التفجير	متر	١,٩٨٢,٦٠	١,٧٢٣,٩٢	٣,٤١٧,٨٤٠,٠٠									٣,٤١٧,٨٤٠,٠٠
جديد	CW١٥، SF٠١	تحديد نطاق الزيادة في الأسعار بالطن	متر					٧٥٢,٠٦	١,٢٠٥,٥٢-	١,٧٢٣,٩٢	٧٥٢,٠٦		١,٢٩٦,٤٨٩,٨٤		١,٢٩٦,٤٨٩,٨٤
جديد	LW٠٣	زيادة السعر للمبنى LW٠٣ و AA٠١	متر					٩٩٣,٠١	١,٢٠٥,٥٢	١,٧٢٣,٩٢	٢١٢,٥١		٣٦٦,٣٤٩,٨٣		٣٦٦,٣٤٩,٨٣
تعدل رقم ٠١	AW٠٦	تصاميم وتفاصيل الضرورية التي يجب ازالتها والاعمدة التي سيتم ترتيبها	طول قياسي	١,٠٠	٣٣,٧٤٤,٠٠	٣٣,٧٤٤,٠٠		--	--	--	--	--	--		٣٣,٧٤٤,٠٠
تعدل رقم ٠١	AW٠٦	تصاميم وتفاصيل الضرورية التي يجب ازالتها والاعمدة التي سيتم ترتيبها	طول قياسي	١,٠٠	٣٣,٧٤٤,٠٠	٣٣,٧٤٤,٠٠		--	--	--	--	--	--		٣٣,٧٤٤,٠٠
تعدل رقم ٠١	LW٠٣	- إعادة تصميم وتفصيل بعد الموافقة على الحل المقترح للعمود المائل. تم تعديل الأحمال الميتة والحية فوق السقف من خلال عمل واحد، وتمت إضافة جزأين من السقف. يختلف السعر بناءً على التصميم النهائي.	طول قياسي	١,٠٠	٨٠,١١٢,٠٠	٨٠,١١٢,٠٠		--	--	--	--	--	--		٨٠,١١٢,٠٠
تعدل رقم ٠١	AA٠١	تختلف الأسعار بناءً على التصميم النهائي. أجريت إعادة تصميم هيكلي بناءً على الحلول والتفاعلات المقترحة. خُفّضت الأحمال الحية للتحقق من التفاعلات النهائية في موقع الجدار	طول قياسي	١,٠٠	٣٤,٢٣٠,٠٠	٣٤,٢٣٠,٠٠		--	--	--	--	--	--		٣٤,٢٣٠,٠٠

| | | |

BSS JOINT VENTURE

PROJECT: Construction of King Faisal Air Academy Project in Majma'a

SUBCONTRACT nr: 8400006604 Amendment #02 dated 26/08/2024

PURCHASE REQUISITION no: n.a.

REQUESTING Dpt.: Construction - BUYER: (Mansour Al Shawaf)

SUBJECT: Final Revised Subcontract Agreement

شركة كليفلاند بريدج للحديد المحدودة
س.ت ٢٠٥٥٠٠٧٩١٨
C.R. 2055007918
Cleveland Bridge Steel Co. Ltd.

Contractor: **BSS Joint Venture –** JV between **Al Bawani - Salini Impregilo – SAJCO**
P.O. Box 99816 – Riyadh 11625 (Kingdom Saudi Arabia)

Subcontractor: **Cleveland Bridge Steel Co. LTD**
P.O Box 10017 Al Jubail 31961 (Kingdom Saudi Arabia)

AL BAWANI salini impregilo

Docusign Envelope ID: D0F95EE7-B5E1-4D84-B5A2-F1D8A418431C

BSS JOINT VENTURE

SUB-CONTRACT AGREEMENT AND GENERAL CONDITIONS

1. **The Main Contract Conditions**
   The Conditions of the Main Contract are based on the Public Projects Saudi Government Contract as amended by the Special and General Conditions and according to the Government Procurement and Tender Law ("GTPL") and the Implementing Regulations of the Procurement and Tender Law.

2. **The Sub-Contract Conditions**
   The Sub-Contract Agreement is the Form of Sub-Contract for design and construct published by the Civil Engineering Contractors Association, November 1998 Reprinted April, 2001 with Amendments) amended by the Particular Conditions and Schedules in order to adapt the form of Sub-Contract for use with the Main Contract Conditions.

****

THIS AGREEMENT made on Wednesday 26th of August 2024

Between

(A) **Al Bawani Company Limited** a company incorporated and existing under the laws of the Kingdom of Saudi Arabia, with Commercial Registration nr. 1010085518, having its registered office at P.O. Box 65697 Riyadh 11566. ("Al Bawani");

(B) **Salini Impregilo S.p.A.** a company incorporated and existing under the laws of Italy, having its Registered Office at Via dei Missaglia, 97 – 20142 Milano, Italy, and having its registered local office, at P.O. Box 99816, Riyadh 11625, KSA and with a Commercial Registration No. 1010164579. ("Salini Impregilo");

(C) **Shibh Al Jazira Contracting Company** a company incorporated and existing under the laws of the Kingdom of Saudi Arabia, with Commercial Registration nr. 1010044185, having its registered office at P.O. Box 2740 Riyadh 11461. ("SAJCO");

All the above companies, which have entered into a joint venture agreement for the Construction of King Faisal Air Academy Project in Majma'a, are collectively referred to as "BSS Joint Venture" or the "Contractor" throughout this agreement.

And

(D) **Cleveland Bridge Steel Co. LTD**, a company incorporated and existing under the laws of the Kingdom of Saudi Arabia, with a Commercial Registration no. 2055007918, having registered Office at P.O Box 10017 Al Jubail 31961, Kingdom of Saudi Arabia (hereinafter called 'the "**Sub-Contractor**') of the other part.

The Contractor and Sub-Contractor hereafter are also referred to singularly as the "Party" and jointly as the "Parties" throughout this Agreement.

WHEREAS
The Contractor has entered into a Contract (hereinafter called the "Main Contract") particulars of which are set out in the **First Schedule** hereto;

AND WHEREAS

- By means of the Sub-Contract 8400006604 dated May 4th, 2021, the Parties have entered into an Agreement about the execution of Hot Rolled Steel Structure Works for Buildings AW05, AW06, LW03, CW15, SF01 & AA01.
- By means of the Sub-Contract 8400006604 Amendment#01 dated March 12th, 2022, the Parties have entered into an Agreement about the execution of additional Works for Steel Structure Works for Buildings AW05, AW06, LW03, CW15, SF01 & AA01.
- During the execution of the Sub-Contract the Parties have revised the Subcontract Agreement to reflect the revised Scope of work in the current Contractual Buildings with the aim to conclude the present Amendment #02 to the Sub-Contract.

AL BAWANI salini impregilo

شركة كليفلاند بريدج للحديد المحدودة
س.ت ٢٠٥٥٠٠٧٩١٨
C.R. 2055007918
Cleveland Bridge Steel Co. Ltd.

BSS JOINT VENTURE

- The provisions of the present Amendment #02 to Sub-Contract supersede all quotations, correspondence, documents whatsoever previously discussed and agreed between the Parties limited to the specific matter of this amendment.

NOW IT IS HEREBY AGREED as follows:

1 The Value of Amendment #02

1.1 The Value of Works to be omission under the present Amendment #02 is (- 6,760,228.50) SAR (in words: Six Million Seven Hundred Sixty Thousand Two Hundred Twenty-Eight Saudi Arabian Riyals 50/100). The Price is presumed and not binding to the Contractor: Sub-Contract Works will be paid according to the actual performed Works against the Sub-Contract Unit Rates Pursuant Appendix #01 herewith.

1.2 By virtue of the present Amendment #02 the Sub-Contract Price pursuant the clause #01 of the Third Schedule is now changed as follows: 'The estimated "Lumpsum" Sub-Contract Price is 20,789,441.50 SAR (in words: Twenty Million Seven Hundred Eighty-Nine Thousand Four Hundred Forty-One Saudi Arabian Riyals 50/100) - V.A.T. not included based upon the Unit Rates and Quantities pursuant the relevant Appendix herewith".

1.3 The Sub-Contract Price is presumed and not binding to the Contractor: Sub-Contract Works will be paid according to the actual performed Works against the Sub-Contract Unit Rates.

2 Appendixes to Amendment #01

- Appendix 01: Amendment #02 – Bill of Quantities

3 Other Provisions

All other Terms and provisions as agreed between the Parties under the Sub-Contract Agreement 8400006604 dated May 4th, 2021, remain unchanged, this amendment being an integral part of it.

شركة كليفلاند بريدج للحديد المحدودة
س.ت ٢٠٥٥٠٠٧٩١٨
C.R. 2055007918
Cleveland Bridge Steel Co. Ltd.

AL BAWANI البواني salini impregilo

BSS JOINT VENTURE

****

In Witness, the Parties have executed this Agreement by their duly authorized representatives here below.

Signed for and behalf of:

BSS Joint Venture – JV between **Al Bawani - Salini Impregilo – SAJCO**

Through its representative:

Mr. Mazen Nayal Title: Project Director DocuSigned by: Hassan Tannir 75F659B823EF44F...

Mr. Naseem Soukar Title: Contracts Manager DocuSigned by: Naseem Soukar 3516682A0F26472...

Mr. Fahad Suleman Title: Shibh Al Jazira Co. Representative DocuSigned by: 9D8F7E2222874E2...

Mr. Samer Moustafa Title: Procurement Manager

Company Stamp

Date:

Signed for and behalf of:

Cleveland Bridge Steel Co. LTD

Through its representative:

Mr. Sayed Elhout Title: General Manager

Company Stamp

Date: 05 - Sept - 2024

شركة كليفلاند بريدج للحديد المحدودة
س.ت ٢٠٥٥٠٠٧٩١٨
C.R. 2055007918
Cleveland Bridge Steel Co. Ltd.

AL BAWANI salini impregilo

Docusign Envelope ID: D0F95EE7-B5E1-4D84-B5A2-F1D8A418431C

Al Bawani – Salini Impregilo - Shibh Al Jazeera

PROJECT: Construction of King Faisal Air Academy Facilities Project in Majma'a (KSA)

BSS JOINT VENTURE

Agreement Ref: 8400006604

Amendment# 3

Subject Final Revised Agreement

Appendix 01: Amendment #02 - Bill of Quantities

Contract Agreement							Variation Order Evaluation						Revised Contract
Agreement Ref.	Activity Code	Description	Unit	Quantity	Unit Rate (SAR)	Amount (SAR)	Tender Quantity	Final Design Quantity	Rate (SAR)	Addition / Ommision Quantity	Addition / Ommision %	Variation Amount (SAR)	Revised Contract (SAR)
Main Agreement	AW05	Structure Type: Hot Rolled Structural steel roof: The cost of fabrication, includes supply and erection of structural steel columns, beams, purlins, insulated sandwich panel (PIR 100mm at Low Rib) roof deck, aluminium cladding to columns and fascia, all fittings (caps, bases, haunches, gussets, end plates, splice plates, brackets, stiffeners, packings and the like); anchorages and wedges for stanchions; anchorages and packings for beams and purlins; shear and threaded studs and other shear connectors; high strength friction grip bolts; holes, countersunk holes and tapped holes for other trades; welded connections; fittings to proprietary members; nuts and washers for steel to steel connections; and other types of bolts and fasteners. U Value for Sandwich Panels shall not exceed 0.25 W/m2.K. Area: 2,039.10 m2	LS	1.00	1,130,247.86	1,130,247.86	-	-	-	-	-	-	1,130,247.86
Main Agreement	AW05	Additional price for Supply, Fabrication, Painting, Erection of Structural Steel Column, Rafter, Portal Frames, Purlins as CBS design and detailing (Optional)	LS	1.00	230,774.02	Rate Only	-	-	-	-	-	-	
Main Agreement	AW05	Additional Price for the Supply and Apply of Intumescent Paint with 2 Hours Fire Resistance.	LS	1.00	52,798.00	52,798.00	-	-	-	-	-	-	52,798.00
Main Agreement	AW05	Additional Price for Rockwool insulation instead of PIR. U Value shall not be more than 0.25 W/m2.K. Thickness shall be derived from the mentioned U Value	LS	1.00	87,998.95	Rate Only	-	-	-	-	-	-	-
New	AW05	Change in the specification of sandwich panels from 0.5mm thickness to 0.70mm thickness outer and inner layers.	LS				-	1.00	236,585.00	1.00	1.00	236,585.00	236,585.00
		Total AW05				**1,183,045.86**						**236,585.00**	**1,419,630.86**
Main Agreement	AW06	Structure Type: Hot Rolled Structural steel roof: The cost of fabrication, includes supply and erection of structural steel columns, beams, purlins, insulated sandwich panel (PIR 100mm at Low Rib) roof deck, aluminium cladding to columns and fascia, all fittings (caps, bases, haunches, gussets, end plates, splice plates, brackets, stiffeners, packings and the like); anchorages and wedges for stanchions; anchorages and packings for beams and purlins; shear and threaded studs and other shear connectors; high strength friction grip bolts; holes, countersunk holes and tapped holes for other trades; welded connections; fittings to proprietary members; nuts and washers for steel to steel connections; and other types of bolts and fasteners. U Value for Sandwich Panels shall not exceed 0.25 W/m2.K. Area: 2,039.10 m2	LS	1.00	1,130,247.86	1,130,247.86	-	-	-	-	-	-	1,130,247.86
Main Agreement	AW06	Additional Price for Rockwool insulation instead of PIR. U Value shall not exceed 0.25 W/m2.K. Thickness shall be derived from the mentioned U Value	LS	1.00	87,998.95	Rate Only	-	-	-	-	-	-	
Main Agreement	Aw06	Additional Price for Rockwool insulation instead of PIR. U Value shall not be more than 0.25 W/m2.K. Thickness shall be derived from the mentioned U Value	LS	1.00	52,798.00	52,798.00	-	-	-	-	-	-	52,798.00
New	AW06	Change in the specification of sandwich panels from 0.5mm thickness to 0.70mm thickness outer and inner layers.	LS				-	1.00	236,585.00	1.00	1.00	236,585.00	236,585.00
		Total AW06				**1,183,045.86**						**236,585.00**	**1,419,630.86**
Main Agreement	SF01	Structure Type: Hot Rolled Structural steel canopy: The cost of fabrication, includes supply and erection of structural steel columns, beams, purlins, sandwich panel (PIR 100mm at Low Rib), roof deck, all fittings (caps, bases, haunches, gussets, end plates, splice plates, brackets, stiffeners, packings and the like); anchorages and wedges for stanchions; anchorages and packings for beams and purlins; shear and threaded studs and other shear connectors; high strength friction grip bolts; holes, countersunk holes and tapped holes for other trades; welded connections; fittings to proprietary members; nuts and washers for steel to steel connections; and other types of bolts and fasteners. Refer to drawing, Section M/ST-109. U Value for Sandwich Panels shall not exceed 0.25 W/m2.K. Area: 17.00 m2	LS	1.00	23,997.71	23,997.71	1.00	-	23,997.71	(1.00)	(1.00)	(23,997.71)	-
Main Agreement	SF01	Additional Price for the Supply and Apply of Intumescent Paint with 1 Hours Fire Resistance.	LS	1.00	1,126.00	1,126.00	1.00	-	1,126.00	(1.00)	(1.00)	(1,126.00)	-
Main Agreement	SF01	Additional Price for Rockwool insulation instead of PIR. U Value shall not be more than 0.25 W/m2.K. Thickness shall be derived from the mentioned U Value	LS	1.00	Rate Only	Rate Only	1.00	-	Rate Only	(1.00)	(1.00)	Rate Only	
		Total SF01				**25,123.71**						**(25,123.71)**	**-**
Main Agreement	CW15	Structure Type: Hot Rolled Supply and install structural steel space truss. The price shall include design and preparing of the design drawings & shop drawings, all steel element (columns, girder, trussed), PVC coated with PVDF (1,550 g/ m2), fabrication, painting, erection including all erection devices & anchor bolts and any material or activity required to finish the work as per drawings and specifications. Area: 4,370.00 m2	LS	1.00	8,176,482.93	8,176,482.93	1.00	-	8,176,482.93	(1.00)	(1.00)	(8,176,482.93)	-
Main Agreement	CW15	Additional Price for the Supply and Apply of Intumescent Paint with 1 Hours Fire Resistance.	LS	1.00	174,916.00	174,916.00	1.00	-	174,916.00	(1.00)	(1.00)	(174,916.00)	-
Main Agreement	CW15	Supply, delivery and installation of Gutter	LS	1.00	9,440.79	Rate Only	-	-	-	-	-	-	
		Total CW15				**8,351,398.93**						**(8,351,398.93)**	**-**

C.R: 2055003918
Cleveland Bridge Steel Co.

Docusign Envelope ID: D0F95EE7-B5E1-4D84-B5A2-F1D8A418431C

Al Bawani – Salini Impregilo - Shibh Al Jazeera

PROJECT: Construction of King Faisal Air Academy Facilities Project in Majma'a (KSA)

BSS JOINT VENTURE

Agreement Ref: 8400006604

Amendment# 3

Subject Final Revised Agreement

Appendix 01: Amendment #02 - Bill of Quantities

Contract Agreement							Variation Order Evaluation						Revised Contract
Agreement Ref.	Activity Code	Description	Unit	Quantity	Unit Rate (SAR)	Amount (SAR)	Tender Quantity	Final Design Quantity	Rate (SAR)	Addition / Ommision Quantity	Addition / Ommision %	Variation Amount (SAR)	Revised Contract (SAR)
Main Agreement	LW03	Structure Type: Hot Rolled Structural steel roof: The cost of fabrication, includes supply and erection of structural steel columns, beams, purlins, **sandwich panel (PIR 100mm at Low Rib), roof deck, aluminium cladding to columns and fascia**, all fittings (caps, bases, haunches, gussets, end plates, splice plates, brackets, stiffeners, packings and the like); anchorages and wedges for stanchions; anchorages and packings for beams and purlins; shear and threaded studs and other shear connectors; high strength friction grip bolts; holes, countersunk holes and tapped holes for other trades; welded connections; fittings to proprietary members; nuts and washers for steel to steel connections; and other types of bolts and fasteners. U Value for Sandwich Panels shall not exceed 0.25 W/m2.K. Area: 7,470.00 m2	LS	1.00	9,714,489.24	9,714,489.24	860.06	1,064.68	9,714,489.24	204.62	23.79%	2,311,209	12,025,699
Main Agreement	LW03	Excluding Sandwich Panel	LS	Included	Included	Included	-	-	971,448.92	-	-23.79%	(231,120.94)	(231,120.94)
Main Agreement	LW03	Additional Sandwich Panel for the Skylight Replacment	LS	Included	Included	Included	6,026.09	7,470.00	201.00	1,444.00	23.96%	290,244.00	290,244.00
Main Agreement	LW03	Additional Price for the Supply and Apply of Intumescent Paint with 2 Hours Fire Resistance.	LS	1.00	2,102,019.00	2,102,019.00	860.06	1,064.68		204.62	23.79%	500,098.98	2,602,117.98
Main Agreement	LW03	Additional Price for Rockwool Sandwich Panel insulation instead of PIR. U Value shall not be more than 0.25 W/m2.K. Size shall be derived from the mentioned U Value	LS	1.00	322,389.47	Rate Only	-	-	-	-	-	-	
New	LW03	Descoping of the Aluminium cladding to columns and fascia (Quantites as per the Tender drawings_	LS	Included	Included	Included	1,815.97	-	480.00	(1,815.97)	(1.00)	(871,665.60)	(871,665.60)
Total LW03						**11,816,508.24**						**1,998,765.87**	**13,815,274.11**
Main Agreement	AA01	Structure Type: Hot Rolled Structural steel : The cost includes design, fabrication, supply and erection of structural steel frames of trass columns, beams, purlins, **Corrugated Metal Deck Sheet Sheet 1 mm Thickness on Strutural Space**, all fittings (caps, bases, haunches, gussets, end plates, splice plates, brackets, stiffeners, packings and the like); anchorages and wedges for stanchions; anchorages and packings for beams and purlins; shear and threaded studs and other shear connectors; high strength friction grip bolts; holes, countersunk holes and tapped holes for other trades; welded connections; fittings to proprietary members; nuts and washers for steel to steel connections; one hour fire rated sprayed material; and other types of bolts and fasteners, and including primer coating and the final coating materials As per structural drawings. Area: 1,030.00 m2	LS	1.00	1,355,485.41	1,355,485.41	132.95	140.84	1,355,485.41	7.89	5.93%	80,442.12	1,435,927.53
Main Agreement	AA01	Excluding Corrugated Metal Deck Sheet Sheet 1 mm Thickness on Strutural Space	LS	Included	Included	Included	-	-	135,548.54	-	-5.93%	(8,044.21)	(8,044.21)
Main Agreement	AA01	Additional Price for the Supply and Apply of Intumescent Paint with 1 Hours Fire Resistance and primer coating and the final coating material as per structural drawing.	LS	1.00	35,392.00	35,392.00	132.95	140.84	35,392.00	7.89	5.93%	2,100.36	37,492.36
Total AA01						**1,390,877.41**						**74,498.27**	**1,465,375.68**
													-
Ammendment No.01	AW05, AW06, SF01, CW15, LW03, AA01	Structural Steel Material including wastage, Bolts, Anchor bolts, blasting material, Packing & welding consumables	MT	1,982.60	1,723.92	3,417,840.00							3,417,840.00
New	CW15, SF01	Desoping of the Price Increase in Tonnage for CW15& SF01	MT				752.06	-	1,723.92	(752.06)		(1,296,489.84)	(1,296,489.84)
New	LW03	Price Increase for Building LW03 & AA01					993.01	1,205.52	1,723.92	212.51		366,349.83	366,349.83
Ammendment No.01	AW05	AW 05 _Design & detailing of end trusses need to be deleted and purlins to be arranged. live loads revised two times and concrete edge distances changed in last revision	LS	1.00	33,744.00	33,744.00	-	-	-	-	-	-	33,744.00
Ammendment No.01	AW06	AW06_Design & detailing of end trusses need to be deleted and purlins to be arranged. live loads revised two times and concrete edge distances changed in last revision.	LS	1.00	33,744.00	33,744.00	-	-	-	-	-	-	33,744.00

C.R. 2051047 Cleveland Bridge Steel

Docusign Envelope ID: D0F95EE7-B5E1-4D84-B5A2-F1D8A418431C

Al Bawani – Salini Impregilo - Shibh Al Jazeera

PROJECT: Construction of King Faisal Air Academy Facilities Project in Majma'a (KSA)

BSS JOINT VENTURE

Agreement Ref: 8400006604

Amendment# 3

Subject Final Revised Agreement

Appendix 01: Amendment #02 - Bill of Quantities

Contract Agreement							Variation Order Evaluation						Revised Contract
Agreement Ref.	Activity Code	Description	Unit	Quantity	Unit Rate (SAR)	Amount (SAR)	Tender Quantity	Final Design Quantity	Rate (SAR)	Addition / Ommision Quantity	Addition / Ommision %	Variation Amount (SAR)	Revised Contract (SAR)
Ammendment No.01	LW03	LW 03_Re-design and detailing after proposed solution of inclined column is approved . Dead & Live loads above roof were changed by One works and two portions of roof was added.* Price varry based on final design.	LS	1.00	80,112.00	80,112.00	-	-	-	-	-	-	80,112.00
Ammendment No.01	AA01	AAOI _Re-design and detailing after proposed solution of Vert ical tr uss is approved. Structural was re-designfor Proposal and reactions. Live loads reduced to check the end reactions at the concrete wall location.	LS	1.00	34,230.00	34,230.00	-	-	-	-	-	-	34,230.00
Total Amendment#01						3,599,670.00						(930,140.00)	2,669,530.00
													-
Total						27,549,670.00						(6,760,228.50)	20,789,441.50

شركة كليفلاند بريدج للحديد المحدودة
س.ت ٢٠٥٥٠٠٧٩١٨
C.R. 2055007918
1
Cleveland Bridge Steel Co. Ltd.